

**Pulaski County Highway Department  
1131 N US 35  
Winamac, IN 46996  
574-946-3942  
574-946-4621 (Fax)**

Specifications Sheet for 2020 CCMG Asphalt Paving Project

Project – County Road 1450 W between 200 S and Culvert at FRATCO. Average width of 27 foot wide and the length is 2.5 miles long.

Furnish and apply tack coat

1 inch wedge and level the surface of the road mentioned above; material does not have to be virgin material

Apply a 1.5” overlay of virgin hot mix asphalt

Apply approximately 1.5 mile of shoulder stone 2-3 feet wide

Furnish Traffic Control

Pulaski County Highway Department will have the roadway prepared for all work to begin. This includes removing the berm and sweeping the road surface.

Bids should be delivered into the Pulaski County Auditor’s Office no later than 3pm on April 5<sup>th</sup>.